



Town of Minto

ADDENDUM NO. 1

From: Town of Minto

Date: Tuesday, April 7, 2026

Addendum No. 1

Town of Minto

Project No.: 6652-26

Tender – Reconstruction of Arthur Street West, Harriston

Closing Date: Tuesday, April 14, 2026 at 2:00:59 p.m.

Please be advised of following clarifications to this project as attached.

I/We hereby acknowledge receipt of this Addendum.

Signed (Must be Signing Officer of Firm)

Name (Print) Date:

Position

Name of Firm

Please update your Tender documents as per the addendums in this document and attach a copy of this addendum page to your submission acknowledging receipt and understanding of the addendum.

TOWN OF MINTO

**PROJECT No. 6652-26
TENDER – Reconstruction of Arthur Street West,
Harriston**

**ADDENDUM NO. 1
Date: Tuesday, April 7, 2026**

QUESTIONS

Question No. 1:

Road cross sections shown on DWG 06 appears to show two conflicting cross sections for STN 1+460 to Sta 1+483.75. Is the first cross section depicting that span perhaps to be labelled as other stations?

Answer No. 1:

The typical section labeled “Typical Section Sta. 1+460 to Sta. 1+483.75” is mis-labeled and should be labeled “Typical Section Sta. 0+087.42 to Sta. 1+400”. The associated quantities are correct in Table B.

Question No. 2:

Is the detail shown on DWG for Subdrain indicative of all subdrain in the tender? Special provision for subdrain item indicates they are to 100mm size and bedded with masonry sand but Detail shows them as 150mm and bedded with clear stone

Answer No. 2:

The subdrain size should be as per Table B (100mm Dia.) and the backfill should be as per Specials 1.31 & 1.32 (Concrete Sand).

Question No. 3:

There seems to be a shortage of information for the precast structures. Can you provide a structure data table or clarify T/G and inverts for the following:

CBMH13, CBMH15, CBMH9A, CBMH7, CBMH4A, CBMH3, TICB8A, CB9B, CB11C, CB11A, CB11B, CB7A, TICB5, TICB1 & CB3A

Answer No. 3:

See attached Structure Data Sheet.

Question No. 4:

Item #1.04 – Unit of Measure looks to be incorrect.

Answer No. 4:

Unit of Measure for Item #1.04 has been updated in the attached updated Form of Tender.

Question No. 5:

Item #1.42 is asking for self leveling MH F&G but later item #1.56 is asking for the MH to be adjusted with a concrete collar. Usually, a concrete collar adjustment utilizes a standard frame and grate. Please clarify.

Answer No. 5:

Item 1.42 has been updated with the appropriate OPSD. See attached updated Form of Tender.

Question No. 6:

Item #1.23 and #1.25 both look to be labeled incorrect on the drawings. 1.23 is 450mm on the FOT but 375mm on the drawings. 1.25 is 375mm on the FOT but 300mm on the drawings. Please clarify.

Answer No. 6:

The drawings are labeled correctly, but quantities for items: 1.23,1.25,1.26,1.27,1.28 & 1.29 have been updated - See attached updated Form of Tender.

ATTACHMENTS forming part of Addendum No. 1 (separate), as follows:

6652-26 – STUCTURE DATA SHEET (2 pages)

6652-26 – Section B – Form of Tender (Addendum No. 1) (14 pages)

Addendum No. 1 (3 pages) + Attachments (16 page) (Total 19 pages)